

## QUOTATION

**NAME OF WORK :-** Providing and Fixing of Window Glass, Repairing work of Tree Otta's, Fixing of Net Bird Near Lift Room, Repairing work of Main loading and unloading Platform and other Misc. repair works at Pune Depot Building, Balbharati Campus, Senapati Bapat Marge, Pune.

Sr. No.	DSR No. 2022-23	Item Specifications	Quantity	Unit	Rate	Amount
1	Building (Bd-T : Water supply and sanitary fittings) 384	Providing and Fixing of Glass plain 5 mm thick including with all required screws,putty(Lambi), U shape clip and nuts etc, complete.	16.00	Sq. Mt.		
2	27.05	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	9.50	Cum.		
3	33.67	Providing and laying Antiskid Ceramic tiles of approved quality of size 30 cm x 30 cm and confirming to IS 15622-2006 (Group-B IIA) for antiskid flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with cement slurry cleaning curing etc. complete.	10.00	Sq. Mt.		
4	24.04	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	5.00	Cum.		
5	Non-Dsr	Providing and Fixing of Bird Net including with all required screws and nuts etc, complete	25.00	Sq. Mt.		

6	23.01	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	1.00	M.T		
7	32.05	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete or brick surfaces, in all position including scaffolding and curing etc. complete.	45.00	Sq. Mt.		
			<b>TOTAL COST</b>			
			<b>G.S.T 18%</b>			
			<b>TOTAL COST OF WORK</b>			

**Seal & Signature of Contractor with address and Mobile No.**